the alfasi hire difference

1 Disconnect on board generator and removal of belt (optional)

2 Work Cover machine design registration
3 12 Months service history

4 Mesh around lower half of basket

5 All controls have legible decals

6 Emergency stop button (one at ground and one on basket)
7 4 Pole lockable isolator with ID decal (red)
8 All main battery cables in split tubing
9 Extreme hose separation hydraulic to electrical (optional)
10 Rubber boot covering all exposed electrical terminals
11 Separation of electrical harnesses using P-clamps (optional)
12 Isolate ground and basket power outlets with isolation padlock (optional)
13 Jump start point (350 Anderson connector)
14 Starter motor lockable isolator with ID decal (yellow)
15 Steel braided fuel hose
16 Turbo sock / cover
17 Pressure relieving radiator cap (mine safe red lever)
18 Guarding on all rotating parts
19 Separation of fuel hoses using P-clamps (optional)
20 Hydraulic accumulator testing (optional)

21 80 ABE minimum 4.5kg fire extinguisher with ID decal

22 2 x Call up ID (45mm thick and 200mm high lettering)

23 Burst protection on hoses at fly boom for operator

24 High visibility tape on basket, boom and machine

25 Separation of hydraulic hoses using P-clips (optional)

26 PPE decals (entire machine)

27 Spiral wrapped lower exposed hydraulic hoses

28 Wheel nut tension indicator
29 Wheel chocks